Product Information Sheet

Whitecroft lighting

General Information

- 1. A qualified electrician, in accordance with IET wiring regulations should carry out connection to mains wiring.
- 2. Luminaire must be isolated before commencing any necessary maintenance work or battery connection.
- 3. Ensure that the rated voltage and frequency requirements are compatible with the available mains supply.
- 4. Do not carry out high voltage insulation test, i.e. 500/1000v this may damage internal components.
- 5. The light source contained in the luminaire shall only be replaced by the manufacturer or a designated service agent or a suitably qualified person.
- 6. Batteries must only be replaced by a qualified electrician once they fail to meet the required duration.
- 7. Dali control cables must be double insulated & have an equivalent rating to the supply cable if applicable. 8. Ensure ceiling is of sufficient strength to support luminaire Fit secondary suspension where necessary.
- Observe ESD precautions during installation.
- 10. All luminaires must be EARTHED. (Excluding Class II luminaires).
- 11. Do not cover recessed luminaires with any thermally insulating materials.
- 12. Do not use the wire suspension to raise or lower the luminaire. (See full instructions for further details.)

Product Specification


Lamp Type	LED
LED Colour	4000K / 3000K
Control gear	DALI, Fixed Output
Emergency	N/A
Finish	White / Silver / Black
Materials	Aluminium, Mild Steel
Weight	1.71kg
Supply	220-240V 50/60Hz
Cable entry	M16 Gland
Connection	0.5-2.5mm²
Ingress protection	IP20
Temperature range	0-25°C
Suspension Detail	Kit Required - MCORDSUSKIT**


Full Installation Instructions

Scan QR code below:



Product Dimensions







055298 - RFV 1

Whitecroft Lighting Limited

Burlington Street, Ashton-under-Lyne, Lancashire OL7 0AX Technical Support 0161 330 6811

technical@whitecroftlight.com http://www.whitecroftlighting.com







Product Installation Instructions



General Information

- 1. A qualified electrician, in accordance with IET wiring regulations should carry out connection to mains wiring.
- 2. Luminaire must be isolated before commencing any necessary maintenance work or battery connection.
- 3. Ensure that the rated voltage and frequency requirements are compatible with the available mains supply.
- 4. Do not carry out high voltage insulation test, i.e. 500/1000v this may damage internal components.
- 5. The light source contained in the luminaire shall only be replaced by the manufacturer or a designated service agent or a suitably qualified person.
- 6. Batteries must only be replaced by a qualified electrician once they fail to meet the required duration.
- 7. Dali control cables must be double insulated & have an equivalent rating to the supply cable if applicable.
- 8. Ensure ceiling is of sufficient strength to support luminaire Fit secondary suspension where necessary.
- 9. Observe ESD precautions during installation.
- 10. All luminaires must be EARTHED.(Excluding Class II luminiares).
- 11. Do not cover recessed luminaires with any thermally insulating materials.
- 12. Do not use the wire suspension to raise or lower the luminaire. (See full instructions for further details.)







055298 - REV 1

Whitecroft Lighting Limited Burlington Street, Ashton-under-Lyne, Lancashire OL7 0AX

Technical Support 0161 330 6811 technical@whitecroftlight.com http://www.whitecroftlighting.com







Product Installation Instructions



Mounting Details





Surface Installation - Steps 1 - 8

Suspended Ceiling Rose Installation - Steps 9 - 16

Maintenance Details - Step 17 - 18


Product Installation Instructions




Surface Installation

Remove product from packaging and inspect for any damage.

(1) Compress springs to release mounting bracket.



(2) Unclip safety cord and detach earth lead from mounting bracket.





Product Installation Instructions




Surface Installation

(3) Remove p-clip & retain the screw. Feed main cable through cable gland





Wrap p-clip around cable and re-attach to mounting bracket with retained screw.




Product Installation Instructions





Surface Installation

5 Fix mounting bracket to ceiling (or other) using suitable fixings. (Allow suitable cable length for maintenance).



6 Reattach safety cord and earth lead. Positioning luminiare for wiring.






Product Installation Instructions




Surface Installation


(7) Wire mains cable. Refer to wiring detail below for wiring details.



WIRING DETAIL



8 Fit luminaire to mounting plate, avoid trapped wires/cables. Ensure both sides clip in place.



Product Installation Instructions




Suspended Ceiling Rose Installation


Remove product from packaging and inspect for any damage.

Pull ceiling rose cover down & unclip earth lead from front plate. Fix ceiling rose to ceiling (or other) using suitable fixings. (Allow suitable cable length for maintenance).

Ceiling rose sold separately



Push ceiling rose cover back in place and leave cable gland loose. Avoid trapped wires/cables.




Product Installation Instructions




Suspended Ceiling Rose Installation

(11) Compress springs to release mounting bracket.



(12) Unclip safety cord and detach earth lead from mounting bracket.




Product Installation Instructions




Suspended Ceiling Rose Installation

13 Feed mains cable through cable gland & tighten.



(14) Reattach safety cord and earth lead to mtg bracket.




Product Installation Instructions




Suspended Ceiling Rose Installation


(15) Wire mains cable. Refer to wiring detail below for wiring details.



WIRING DETAIL



Fit luminaire to mounting plate, avoid trapped wires/cables. Ensure both sides clip in place.




Product Installation Instructions





Maintenance Details

(17) Use flat tool to release springs for maintenace.



For internal maintenace slide geartray away from aluminium body, loosen screws to release.





Emergency Luminaire

Maintenance, Commissioning & Fault Finding Guide



BATTERY STORAGE/CARE DETAILS

Optimal storage conditions (when not in service and batteries disconnected)

· NiCd +5°C to 25°C (6 months onsite maximum)

- NiMh +5°C to 25°C (3 months onsite maximum)
- · LiFEP04 +5°C to 25°C (6 months onsite maximum)

Old batteries must be handled and disposed of by specialist disposal experts. Under no circumstances should they be pierced or incinerated.

Do not put the luminaire into emergency mode until the batteries are fully charged

MAIN CAUSES FOR PREMATURE BATTERY FAILURE:

- 1)Over cycling of batteries for example caused by an unstable mains supply. Batteries are designed to carry out 3 4 full discharges per year. Over cycling will reduce the capacity and hence life.
- 2) Leaving connected batteries in a discharged state (maximum 2 weeks).
- 3) High ambient temperatures (greater than the ambient specified by Whitecroft lighting)
- 4) Repeated partial discharging and recharging of batteries (memory effect)

EMERGENCY SUPPLIES

Power to energise emergency luminaires can come from integral batteries within the luminaire (self-contained) or from a remote Central Battery system or Static Inverter. This power supply is intended to energise the emergency circuit within any emergency luminaire upon failure of the normal supply.

Integral battery emergency luminaires indicate 'batteries are charging' generally by use of an indicator LED mounted in a visible location on the luminaire. When the indicator LED is solid green, the batteries are charging.

Emergency luminaires generally have internal supply connections; Permanent Live (orange), Switched Live (brown), Neutral (blue), and Earth (green/yellow),

As detailed in BSEN50172:2004 (BS5266-8:2004)

- Monthly function test (30s) to check luminaires are functioning correctly (unless detailed differently in commissioning procedure)
- Annually full duration test to check the luminaires are functioning correctly and meet their full duration
- Emergency testing results must be documented and be available for inspection.

Inspection / fault finding work must be carried out by a suitably electrically qualified person.

Initial checks must include continuity of fuses and integrity of internal/external wiring.

Please read BATTERY STORAGE/CARE details in this leaflet before continuing.

CAUTION: Even if the power supply to the emergency luminaire may be disconnected, there may still be high voltages inside the fitting. Disconnect batteries when maintaining internal wiring.

- A. LED indicator non-operational and does not work in Emergency mode.
 - Check that the permanent 230v supply is present in the luminaire.
 - Check the batteries are properly connected.
 - 3. Replace the batteries with known working units.

 - Replace the inverter ensuring you change it 'wire for wire'. If the luminaire still does not function please call Whitecroft Technical. 5.
- B. Luminaire functions in Emergency mode but will not function in Standard mode.

 - Check that the Switched Live is present.
 Check that the Switched and Permanent Supplies are correctly connected. 2.
 - Check that there is 230v at the 'Live Out' terminal of the emergency inverter.
 - If the luminaire still does not function please call Whitecroft Technical.
- C. LED indicator illuminated but luminaire does not work in Emergency mode.
 - Check light engines in emergency circuit are working
 - 2.
 - Replace the batteries with known working units. Replace the inverter ensuring you change it 'wire for wire'.
 - If the luminaire still does not function please call Whitecroft Technical.
- D. LED indicator not illuminated but luminaire functions in all other respects.
 - Check the cable to the LED indicator; make sure it is properly terminated and has not been trapped or cut.
 - Replace the LED indicator with a known working one
 - Replace the inverter ensuring you change it 'wire for wire' If the luminaire still does not function please call Whitecroft Technical.
- E. Luminaire will not last 3 hour duration test.
 - Check that the batteries have been charged for at least 24 to fully charge
 - Check that the Switched and Permanent Supplies are correctly connected.
 - 3 Replace the batteries with known working units.
 - 4
 - Replace the inverter ensuring you change it 'wire for wire'. If the luminaire still does not function please call Whitecroft Technical.

EMERGENCY LUMINAIRE COMMISSIONING

Battery activation

- For new NiCd, NiMh & LiFEP04 batteries activation of the cell is required to ensure specified design life.
- If the emergency luminaire does not pass the initial 3hr duration test a further full charge and discharge cycle may be required to activate the battery chemistry.

PROCEDURE

STANDARD EMERGENCY

- Connect the battery once a stable mains supply is present
- Allow the battery to charge for a period of 24hrs Perform a full manual discharge test (minimum 3 hrs.)
- 3.
- If the emergency luminaire does not pass the initial 3hr duration test a further full charge and duration test (this test can be used as the scheduled EM test)
- 5 If the luminaire does not pass 3 hour test contact Whitecroft Technical for assistance.

EASY-TEST/SELF-TEST

- Connect the battery once a stable mains supply is present
- 2. Allow the emergency luminaire to complete its self-commissioning phase which charges the battery for 24hrs, followed by a 3hr duration test.
 - If the luminaire successfully completes this test, the indicator LED will be solid green If the emergency luminaire does not pass the initial 3hr duration test, allow the battery to charge a further 24hrs and then do a manual 3hr duration test
- If the luminaire fails this duration test then contact Whitecroft Technical for assistance

DALITEST

- Connect the battery once a stable mains supply is present
- Allow the emergency luminaire to complete its self-commissioning phase which charges the battery for 24hrs, followed by a 3hr duration test. If the luminaire successfully completes this test, the indicator LED will be solid green OR if a DALI bus is connected and the luminaire has been commissioned the self-commissioning duration test can be stopped and a scheduled duration test can be performed using DALI commands.
- If the emergency luminaire does not pass the 3hr duration test, allow the battery to charge a further 24hrs and then do a manual 3hr duration test
- If the luminaire fails this duration test then contact Whitecroft Technical for assistance.

EMERGENCY COMEPS DALI TEST



Application

Low profile emergency lighting module with DALI interface and automatic testing facility to cover 3 hour duration operating from batteries.

DALI interface terminals are provided to allow control and monitoring via a separate controller. With no DALI bus connected the unit operates in self-test mode with testing being conducted on a weekly functional and 52 week duration basis with adaptive duration testing feature to minimise risk.

Fitted with the unique easy addressing feature which uses the LED to indicate the DALI address during commissioning.

Monitoring

DALI interface for controlled monitoring and reporting.

During operation the battery, lamp and charge conditions are monitored along with functional and duration testing.

In the event of failure the bi-coloured LED will indicate the nature of the fault. This it will continue to do until the fault has been remedied. The testing regime will then continue.

Testina

When a DALI bus is not connected or when a command has not been received the COMEPS will operate in the self testing mode and will conduct tests in accordance with the default times stored in the EEPROM. However it should be noted that in this case the delay time is set as default zero and all units could test at the same time. Test times can be changed with a command over the DALI bus.

Addressing

The COMEPS includes the easy addressing system which allows addressing and identification by using the bi-colour LED in conjunction with the COMEPS ADDRESS tool. Binary address codes given by the LED can be simply converted to the DALI addresses 0 to 63. For single handed addressing using this method it is necessary to send a broadcast ident command every 3 to 9 seconds. During this command the main fluorescent lamp will be switched off and the LED will flash the 6 bit binary address preceded by a 3 second start indication period.

Functional test

The time of day and frequency of the 30 seconds function test can be set by the DALI controller. If the COMEPS unit is not connected to a DALI bus or has not received a DALI command the test will default to 30 seconds duration on a weekly basis.

Duration test

Test times can be set by the DALI controller. If the COMEPS unit is not connected to a DALI bus or has not received a DALI command the test will be conducted every 52 weeks.

Prolong time

Prolong time can be set by the DALI controller. This is the delay time between return of the mains supply and the end of the emergency operation. The default prolong time is set as 0 minutes as specified within the DALI standard.

Battery

Recommended charge time is min. 24h. Battery should be fully charged before any emergency tests are performed.

STATUS INDICATION - TRIDONIC INVERTER

LED STATUS
Permanent green System OK

Fast flashing green Functional test underway

Slow flashing green Commissioning/Duration test underway

Permanent red Lamp fault
Fast flashing red Charging fault
Slow flashing red Battery fault

Double pulsing green Battery fault Inhibit mode

Off Loss of mains/battery supply

STATUS INDICATION - ELP INVERTER

LED STATUS

Permanent green System OK
Fast flashing green Functional test underway

Slow flashing green Commissioning/Duration test underway

Permanent red Lamp/LED fault
Fast flashing red Charging fault
Slow flashing red Battery fault
Double pulsing green Inhibit mode
Green with double off pulse
Alternate green/red flash Identification Mode

Off Loss of mains/battery supply

STATUS INDICATION - MACKWELL INVERTER


LED STATUS

Permanent green System OK
Fast flashing green Functional test underway

Slow flashing green Commissioning/Duration test underway

10 second green blink Standby mode
Fast flashing red Lamp/LED fault
Slow flashing red Battery/Charging fault
Off Loss of mains/battery supply

DALI LUMINARES CONNECTIONS FOR COMEPS AND DALI LUMINAIRES



Note: It is imperative to add the links shown below if using DALI dimming and emergency test on the same addressable control circuit.

ORGANIC RESPONSE LUMINAIRE WITH COMEPS (DALI) LUMINAIRE CONNECTIONS

The luminaire is supplied with terminal connections for both the COMEPS inverter and Organic Response node. The Organic response terminal are supplied with the connections blocked to stop inadvertent connection. If the luminaire is to be used for emergency reporting on the Organic Response Portal system, then the terminations should be unblocked and connected as below.



Organic Response Terminations as supplied blocked to prevent inadvertent connection.




Image to show DALI links for Organic Response DALI system

EASY TEST



Application

Whitecroft Easytest is an intelligent testing system, which can monitor and test self-contained emergency lighting luminaires.

The system tests luminaires in line with current legislation for self-contained non-maintained emergency applications with battery duration up to 3 hours.

Intelligence

The easytest unit is a stand-alone intelligent module, which can be integrated into virtually any Whitecroft emergency luminaire.

Each intelligent luminaire has EITHER a bi-coloured LED OR TWO LED's to indicate unit 'on test' or 'failure' diagnostic information in addition to 'battery charging'.

Monitoring

During operation the battery, lamp and charge conditions are monitored along with functional and duration testing.

In the event of failure the LED (s) will indicate the nature of the fault until the fault has been remedied. The testing regime will then continue.

AUTOMATIC TESTING

Commissioning Test

A full commissioning test is carried out automatically after permanent connection of the supply. The easy commissioning feature will set the initial test day and time to ensure random testing of units.

Functional Test

Functional tests are carried out for 30 seconds on a weekly basis.

Duration Test

A full duration test is carried out yearly to check the capacity of the batteries.

STATUS INDICATION (Standard LED configurations)							
Single Bi-	colour LED	STA TUS	Two separate LED's				
GREEN	RED		GREEN	AMBER			
ON		System OK	ON	OFF			
FLASHING		Functional test underway	ON	OFF			
	ON	Lamp fault	ON	FLASHING			
	SLOW FLASH	Battery fault	OFF	FLASHING			
	FAST FLASH	Charging fault	OFF	FLASHING			

NOTE: IEC 60073 recommends that the charge indicator LED should be Green to indicate System OK. The above table conforms to those recommendations.

It is possible to reverse the bi-colour LED connections to swap Green and Red indications and it is also possible to have an alternative Red + Amber LED pair for compatibility with earlier product.

WIRE ROPE SUSPENSION




Installation of Wire Rope Suspension System of Luminaires

Whitecroft Lighting luminaires must be installaed in accordance with the relevent installation instruction and as guidance the latest version of BSRIA Code of Practice 22 - Wipe Rope Suspension Systems.

Do not use the wire suspension to raise or lower the luminaire during installation as this may result in damage to the clutch mechanism.

The clutch should only be adjusted when supported and under no mechanical load.



Warning Symbol Key





Do not cover the luminaire with thermal insulation as may cause product to overheat and cause damage



High voltage warning against risk of electric shock



Falling objects in areas where at risk from falling object hazards



General Warning used to denote areas of caution



Hot surface to warn others around areas where there are any hot surfaces present



High temperature displayed around areas where it is necessary to warn people about the dangers posed from any high temperature



5019 Protective earth (ground) to identify any terminal which is intended for connection to an external conductor for protection against electrical shock in case of a fault, or the terminal of a protective earth (ground) electrode



ESD Electrostatic Discharge is intended to identify devices and assemblies that are susceptible to ESD

055298

M3 C88 - INSTALLATION LEAFLET

NPD 170 - MIRAGE 3 SURFACE

APPROVAL STATUS REV DATE DRAWN BY APPROVED BY 1026 Matthew Freeman Jack Johnson

Document Revision							
Revision Number	Revision Description	Technical Sign-off	Lab Sign-off	Category Manager Sign-off			
1	New Template Generated	M.BOWDEN	L.TUPMAN	I.WILKIE			
2	Added Page for Checklist + Sign Off	M.BOWDEN	L.TUPMAN	I.WILKIE			
3	Changed 'IEE' Spec. to 'IET'.	M.BOWDEN	L. TUPMAN	T. BOWES			

Check List				
Task	Complete			
Product name inserted in the title box				
Additional general information added if required				
All product specification table is filled in correctly				
QR code is generated and working				
Overall product dimension views are shown clearly and dimension are easy to read				
Revision and Date are filled in				
Are warning symbols used where applicable				
Is there a view of the sencondry suspension point location				
Is there a view of the drainage path/ hole and labeled up				
Are any hot surface marked up				
Are the minium void dimension shown and warning shown do not insulate				
Are the cable entry points clearly marked up				
Are the suspension points clearly marked up with dimesions				
Is it clear how many person install is required				
If required have all specific IK notes/views been added				
Any specific orientations that the product can not be mounted in are noted clearly				
If required have all specific IP rating notes/views been added				
Have views of how to wire into the product been shown.				
If required, has installation into all typical ceiling grids been shown.				
If required, have maxium and minium ceiling installation thickeness been noted / view.				
If emergency, has access to the batteries and connections been shown.				
Any accessories supplied sepperatly shown with part code, and how to install.				
Any easy scratch surfaces noted.				
Any specific cleaning product required noted.				
Any specific torque noted if required for maintaince / installation.				
All tools required for installation / maintainance listed.				